

# झोपडपट्टी पुनर्वसन प्राधिकरण

पुणे व पिंपरी चिंचवड क्षेत्र, पुणे  
मुथ्या चेंबर्स, सेनापती बापट रोड, पुणे-१६.

## लेखा विभाग

झोपडपट्टी पुनर्वसन प्राधिकरण, पुणे या कार्यालयाच्या अधिका-यांसाठी जुन्या पार्टिशन मध्ये फेरफार करुन केबिनची दुरुस्ती करणे, नविन टेबल तयार करणे व टेबलाजवळील कपाटे तयार करणे इत्यादी कामाचे दरपत्रक मागविणेबाबत.

जाहिरात क्र.: - /२०१९

दिनांक:- ३१/१२/२०१९

पुरवठादाराकडून खालील स्पेसिफिकेशनप्रमाणे दरपत्रक व अंदाजपत्रकानुसार सीलबंद (QUOTATION) मागविण्यात येत आहेत.

अ.क्र.	तपशिल, दरपत्रक (QUOTATION)
१.	झोपडपट्टी पुनर्वसन प्राधिकरण, पुणे या कार्यालयाच्या अधिका-यांसाठी जुन्या पार्टिशन मध्ये फेरफार करुन केबिनची दुरुस्ती करणे, नविन टेबल तयार करणे व टेबलाजवळील कपाटे तयार करणे इत्यादी कामाचे दरपत्रक मागविणेबाबत

## स्पेशिफिकेशन:-

No	Quantity	Description of Item	Rate (in Rs.)	Unit	Amount (in Rs.)	Amount put to Quotation
1	66.40 Sqm	Removing old wooden or glass partion etc.at engineering incharge etc.complete.	100	Per Sqm.	6640.00	
2	28.728 Sqm	Providing & fixing FULL HEIGHT LAMINATED PARTITION 76 mm thk. Made up of 18 mm thk. Commercial (ISI-303) plywood 25 x 50mm width frame work and both face covered with 12mm thick commercial (ISI-303) ply treated with anti termite treatment and both side finish with 1.00mm thick Laminates confirming to (ISI 2046) and 8.00mm thick clear Glass as per architectural Design & Drawing including all material, Hardware, labour and as directed by Engineer-in-charge etc complete.	4,453.00	sqm.	127929.66	
3	5.49 Rmt.	Proving & fixing Cabin Room Table made up of 18 mm thk.commercial (ISI-303) plywood & both sider finish with 1.00mm thk Laminate confirming to (ISI-2046) as per Architectural Design & Drawing including all materials, Hardware labour and as directed by engineer-in-charge etc. Complete.	12,374.00	Rmt.	67933.26	
4	4.05	Runner Table window sill level	12,374.00	Rmt	50114.70	

	Rmt	Providing & fixing runner Table below window sill level made up of 18mm thk. Commercial (ISI-303) plywood treated with anti termite treatment and both side finish with 1.00mm thick Laminates confirming to (ISI 2046) and inside 0.9mm thick white laminate as per architectural Design & Drawing including all material, Hardware, labour and as directed by Engineer-in-change etc complete.				
5	3.00 sqm	Glass Door Providing & fixing Glass door made up of 18mm thk. Commercial (ISI-303) plywood 25 x 50 mm width frame work and both face covered with 12mm thick commercial (ISI-303) plywood treated with anti termite treatment and both side finish with 1.00mm thick Laminates confirming to (ISI 2046) up to sill level and 8.00mm thick clear Glass above sill level covered with Garware film and as per architectural Design & Drawing including all material, Hardware, labour and as directed by Engineer-in-change etc complete.	4,453.00	sqm	13359.00	
					265977.00	

**अटी व शर्ती :-**

- १) उपरोक्त अंदाजपत्रक व स्पेसिफिकेशन नुसार आपले दर सादर (quote) करुन कोटेशन सादर करावीत.
- २) सेवा पुरवठादाराने दिलेले दर सार्वजनिक बांधकाम दर सुचीनुसार व सर्व करांसहित (GST) असावेत.
- ३) दरपत्रके सादर करण्याअगोदर सेवा पुरवठादारांनी स्थळ पाहणी करुनच दर सादर करावेत.
- ४) सेवा पुरवठादाराने कार्यालयाच्या तांत्रिक विभागाच्या सुचनेनुसार काम करावे.

वरील स्पेशिफिकेशन व अटी शर्तीप्रमाणे मोहरबंद दरपत्रक झोपडपट्टी पुनर्वसन प्राधिकरणाच्या कार्यालयात दि.०१/०१/२०२० ते दि.०६/०१/२०२० पर्यंत कार्यालयात दु. ०३.०० वाजेपर्यंत स्विकारले जातील.

उपसंचालक (लेखा)  
झोपडपट्टी पुनर्वसन प्राधिकरण  
पुणे व पिंपरी चिंचवड क्षेत्र, पुणे